

Tender Notice Number :- SBC/34/(1)/2021 DATED 31/07/2021 , Last date of Submission :- 09/08/2021 by 2 p.m./Date of Opening of Tender 09/07/2021 at 3.00 p.m. (Tender details will be available in College & Tender Notice published website & Notice Board

For inviting sealed quotation / tender from bonafide contractor for fire safety(those who has been passed experience about the work) of the existing construction (SILIGURI B.ED COLLEGE,P.O.KADAMTALA.DT DARJEELING)of G+2 storied building Plot no-LR- 785(P),RS-616(P), KHATIAN NO 12352. Rates will be submitted as per following specifications & work should be completed by 30 days after issuing the work order , Firm registration(by the Govt) & tax should be clear update. The College Building Committee have full right to cancel and tender papers without reason.

SL NO	ITEM NAME	QTY	RATE	AMOUNT
1	Supply, Installation of Electric Motor driven main Fire Pump 3 HP with all fittings & accessories	1		
2	Supply, Installation of GET Valve as per IS:14846 PN1.6. 80NB	1		
3	Supply, Installation of Non Return Valve as per IS:5312 PN1.6. 80NB	1		
4	Supply, Installation of Pressure Gage miter with accessories	1		
5	Supply, Installation of Ari realise valve	1		
6	Starter for Pump with all accessories &	1		
7	Cable for Pump House(6mm non R-Mar cable) 1 coil(apx)	1		
8	Supply, Installation of Hydrant Valve single headed with 80mm inlet & 63mm outlet instantaneous female coupling single outlet	1		
9	Supply, Installation of 63mm Dia CP Hose Pipe 15meters length with male/female coupling(SS)	1		
10	Supply, Installation of Branch pipe with 20mm nozzle(SS)			
11	Supply, Installation of glass fronted 18 SWG MS Hose Cabinet along with all accessories suitable to accommodate 2(two) nos. Hose of 63mm x 15 meter long & Branch pipe.	1		
12	Supply, Installation of Fire Brigade Inlet connecting Head 2 way	1		
13	Supply, Installation of Fire Hose Reel generally as specified using MS pipe ISI Mark 30 miter (all pipe & fitting together with flange neoprene gasket nut/bolts	2		
14	Supply, & Laying of generally as specified using MS pipe.ISI Mark, TATA PIPE (L)			
	100MB	18mtr		
	80mb	6mir		
15	Miscellaneous expences (labor charge and caring charges etc			
16	Pvc water tank including fittings (2000+3000)50000lts			

Bibhuti Bhusan Sarangi

Dr. Bibhuti Bhusan Sarangi
Principal
Siliguri B.Ed. College